

PROJECT TITLE: CONSTRUCTION OF WATER SUPPLY SYSTEM FOR ESCALANTE WATER DISTRICT (STRAIGHT CONTRACT LABOR & MATERIALS)

ABC: ₱ 10,483,400.90

INVITATION TO BID:

Item #	Qty	Unit	Item Description	Unit Cost	Total Cost
			A. Source Development		
0001	12	m.	Construction of Dug Well		
			B. Pumping Facilities		
			(Montemayor Pumping Station No.1)		
0002	40	lm.	Perimeter Fencing		
0003	9	Sq.m	Pumphouse		
0004	1	set	Electro-Mechanical Facilities		
0005	1	unit	20KVA Diesel Engine Drive Generator Set		
			(Montemayor Pumping Station No.2)		
0006	40	lm.	Perimeter Fencing		
0007	9	Sq.m	Pumphouse		
0008	1	set	Electro-Mechanical Facilities		
0009	1	unit	20KVA Diesel Engine Drive Generator Set		
			(Mocabog Pumping Station)		
0010	40	lm.	Perimeter Fencing		
0011	9	Sq.m	Pumphouse		
0012	1	set	Electro-Mechanical Facilities		
0013	1	unit	15KVA Diesel Engine Drive Generator Set		
			C. Treatment Facility		
0014	1	unit	Hypochlorinator at Montemayor Pumping Station No.1		
0015	1	unit	Hypochlorinator at Montemayor Pumping Station No.2		
0016	1	unit	Hypochlorinator at Mocabog Pumping Station		
			D. Pipelaying, Interconnection, and Miscellaneous Works		
0017	560	lm	Pipelaying 150mm dia. uPVC Pipe, S-10		
0018	835	lm	Pipelaying 100mm dia. uPVC Pipe, S-10		
0019	1	set	100mm dia. Gate Valve (Interconnection Detail No.2 at Sheet CD-1)		
0020	1	set	100mm dia. Gate Valve (Interconnection Detail No.3 at Sheet CD-1)		
0021	2	sets	100mm dia. Gate Valve (Interconnection Detail No.4 at Sheet CD-2)		
0022	1	set	150mm dia. Gate Valve (Interconnection Detail No.4 at Sheet CD-2)		
0023	1	set	100mm dia. Gate Valve (Interconnection Detail No.5 at Sheet CD-3)		
0024	32	Sq.m	Concrete Pavement Demolition (thickness=200mm)		
0025	7	Cu.m	Concrete Surface Restoration (thickness=200mm)		
			Sitio Mocabog, Brgy. Washington Resettlement Site		
0026	2835	lm	Pipelaying 100mm dia. uPVC Pipe, S-10		
0027	650	lm	Pipelaying 75mm dia. uPVC Pipe, S-10		
0028	2	sets	100mm dia. Gate Valve (Interconnection Detail No.6 at Sheet CD-3)		
0029	1	set	100mm dia. Gate Valve (Interconnection Detail No.7 at Sheet CD-5)		

0030	1	lot	Box Culvert Pipe Crossing, 100mm dia.		
0031	32	Sq.m	Concrete Pavement Demolition (thickness=200mm)		
0032	7	Cu.m	Concrete Surface Restoration (thickness=200mm)		
Sitio Bontoranon, Brgy. Washington Resettlement Site					
0033	1095	lm	Pipelaying 100mm dia. uPVC Pipe, S-10		
Item #	Qty	Unit	Item Description	Unit Cost	Total Cost
0034	3	sets	100mm dia. Gate Valve (Interconnection Detail No.9 at Sheet CD-6)		
0035	1	set	100mm dia. Gate Valve (Interconnection Detail No.10 at Sheet CD-7)		
0036	2	sets	100mm dia. Gate Valve (Interconnection Detail No.11 at Sheet CD-7)		
0037	1	set	75mm dia. Gate Valve (Interconnection Detail No.11 at Sheet CD-7)		
0038	1	set	75mm dia. Gate Valve (Interconnection Detail No.12 at Sheet CD-8)		
x-x-x-x Nothing Follows x-x-x-x					

PRE-BID CONFERENCE: **DECEMBER 3, 2024 9:00 A.M.**

OPENING OF BIDS: **DECEMBER 17, 2024 10:00 A.M.**

LOCATION: **BUDGET OFFICE, ESCALANTE CITY GOVERNMENT CENTER (THE PENTAGON)**

BIDDING